

Room	Wide	Length	ceiling height	lecks slab height	total sq.f.	2x2 tile	2x4 tile	w/a linear	hain12 piece	tee 4"	tee 2"	anchor for slab	wire pieces 6'	wire pieces 12'
101.00	7.75	7.25	10.00	16.00	56.19	15.45	7.73	31.50	1.99	5.62	11.24	8.68	8.68	8.68
102.00	8.00	93.25	10.00	16.00	746.00	205.15	102.58	212.63	26.42	74.60	149.20	115.29	115.29	115.29
103A	17.00	20.50	10.00	16.00	348.50	95.84	47.92	78.75	12.34	34.85	69.70	53.86	53.86	53.86
103B	19.50	20.50	10.00	16.00	399.75	109.93	54.97	84.00	14.16	39.98	79.95	61.78	61.78	61.78
105.00	10.50	20.50	10.00	16.00	215.25	59.19	29.60	65.10	7.62	21.53	43.05	33.27	33.27	33.27
106.00	12.50	20.50	10.00	16.00	256.25	70.47	35.23	69.30	9.08	25.63	51.25	39.60	39.60	39.60
107.00	11.00	20.50	10.00	20.50	225.50	62.01	31.01	66.15	7.99	22.55	45.10	34.85	34.85	34.85
108.00	10.50	20.50	10.00	20.50	215.25	59.19	29.60	65.10	7.62	21.53	43.05	33.27	33.27	33.27
109.00	4.00	7.00	10.00	20.50	28.00	7.70	3.85	23.10	0.99	2.80	5.60	4.33	4.33	4.33
110.00	12.00	20.50	10.00	20.50	246.00	67.65	33.83	68.25	8.71	24.60	49.20	38.02	38.02	38.02
111.00	14.50	21.00	10.00	20.50	304.50	83.74	41.87	74.55	10.78	30.45	60.90	47.06	47.06	47.06
112.00	1.00	1.00	10.00	16.00	1.00	0.28	0.14	4.20	0.04	0.10	0.20	0.15	0.15	0.15
113.00	1.00	1.00	10.00	16.00	1.00	0.28	0.14	4.20	0.04	0.10	0.20	0.15	0.15	0.15
114.00	20.50	21.00	10.00	16.00	430.50	118.39	59.19	87.15	15.25	43.05	86.10	66.53	66.53	66.53
115.00	29.50	50.50	10.00	20.50	1,489.75	409.68	204.84	168.00	52.76	148.98	297.95	230.23	230.23	230.23
All are in PIECES					4,963.44	1,364.95	682.47	1,101.98	175.79	496.34	992.69	767.08	767.08	767.08